

REQUEST FOR QUOTE

Quotes must be submitted by email to the email address below

AGENCY: Illinois Department of Public Health

CONTACT: Sean McAuliff

EMAIL: sean.m.mcauliff@illinois.gov

SPECIFICATIONS	
Contract Length	From date of execution to 4/30/2022.
Required Services	<p style="text-align: center;">HARWOOD HEIGHTS COVID-19 COMMUNITY-BASED TESTING SITE SNOW REMOVAL AND SALTING SERVICES</p> <p style="text-align: center;">Quotes are due not later than November 5, 2021 3:00 pm Central Standard Time</p> <p>The Illinois Department of Public Health (IDPH) is seeking quotes from vendors to perform snow removal at the Harwood Heights COVID-19 Community-Based Testing Site, located at 6959 West Forest Preserve Road, Chicago, Illinois. Please refer to Exhibit A for exact snow/ice removal location on page 3 of this document</p> <ul style="list-style-type: none">• Vendor will have had a minimum of three (3) years previous experience in commercial snow plowing and removal services.• Vendor will be responsible for snow removal services (snow plowing, snow blowing, snow shoveling, and snow/ice removal) and salting services at the site to ensure safety of visitors and staff.• Vendor will be responsible for removing snow and ice across the whole site, including parking lots, sidewalks, and testing lanes. See attached Exhibit A for view of the site.• Vendor will provide services/surface treatments as often as necessary to mitigate snow and/or ice accumulations. It is expected that snow accumulations shall not exceed one (1) inch on the parking lot, sidewalks, and other surfaces and staircases during testing hours (7:00 am-3:00 pm). All snow/ice accumulation occurring outside normal working hours must be cleared, treated, and service complete prior to 6:00 am. In the event it is still snowing/icing at the start of business, accumulations must not exceed the above accumulations.• After the plowing/removal of snow and/or ice, salt or other deicing materials shall be effectively applied to all such surfaces with the intent to prevent the build-up of ice and thereby reduce the risk of pedestrians slipping or falling. Only non-corrosive treatments such as <i>calcium chloride or equal</i> may be used.• Site will be pre-treated when inclement weather predictions include predictions of ice or snow.• Vendor will take preventative measures to avoid ice build-up and shall take appropriate action to remove ice build-up on any vehicular and pedestrian surfaces mentioned herein.

	<ul style="list-style-type: none"> • Vendor will be liable for any repairs to the site caused by any snow plowing or snow/ice removal services, including but not limited to light poles, fences, lawn and landscaped areas, parking facilities or pedestrian areas. • Vendor will train, guide, and supervise staff to minimize property damage during operations. • Vendor will be responsible for providing all labor, equipment, and materials, including but not limited to shovels, ice picks, plows, backhoe, dump trucks, snow blowers, salt, calcium chloride, any deicers. These must be provided in sufficient number and quality to efficiently clear ice/snow. • Vendor will designate a liaison or contact person to communicate with IDPH on any scheduling or snow removal issues that interfere with contracted services resulting from this RFQ.
QUOTE	\$ Per daily snow and ice removal and salting services.

Note to Vendor: The quote must be valid for 90 days from date of submission and must include all expenses. We reserve the right to reject all offers and to reject individual offers for failure to meet any requirement.

Company Name: _____

Signature: _____ **Date:** _____

Printed Name: _____

Title: _____

Exhibit A: Snow/ice removal and salting location. This shall be done for the area entirely within the red lines below

